

# Project Profile

Shoreview Pervious Streets-Woodbridge Neighborhood  
Shoreview, MN  
Constructed: June-Sept 2009

## *Scope of Work:*

Rebuild recent annex subdivision rural profile roads to meet current city requirements.

## *Design Factors:*

- Fire and garbage truck loads
- No storm sewer system was present in existing pavement
- Eliminate storm water run off to adjacent lake

## *Concrete:*

Pervious mix with 3/8 aggregate.

## *Placement:*

Allen triple roller screed between CIP curb and gutter section on top of rock recharge base. Wet curing blanket placed on surface following finish. Soft cut transverse and longitudinal joints.



July 2009

*Update:*